

SAFETY, HEALTH & ENVIRONMENTAL HAZARD INFORMATION BOX. The hazards noted below are in addition to the normal hazards and risks faced by a competent contractor when dealing with the types of works detailed on this drawing. CONSTRUCTION RISKS: Deep Trenches Unforeseen Services Leptospirosis DEMOLITION RISKS: Leptospirosis Notes: 1. DO NOT SCALE FROM THIS DRAWING. 2. All dimensions are in millimetres Unless Noted Otherwise (u.n.o.) 3. Drawing is to be read in conjunction with all relevant architect's drawings. Any inconsistencies should be reported to PRP immediately. 4. All levels and dimensions are to be checked on site before any work commences. 5. The Health and Safety at Work act is to be complied with at all times. Attention is drawn to the wearing of hard hats, reflectorised clothing, and the use of any other required safety equipment. Drainage: 1. Invert levels of existing manholes to be checked on site prior to commencing any drainage works. For positions of all rainwater pipes & foul outlets refer to Architect's drawings. All joints between precast manhole components shall have a minimum uncompressed thickness of 10mm of proprietary bitumen or resin mastic sealant. Storm & foul branch connections are to be laid at gradients of between 1:10 & 1:80 All in-situ concrete shall be minimum grade GEN3. Precast concrete cover & reducing slabs to be heavy duty reinforced concrete to BS 5911. Rising mains shall be black MDPE SDR11 as WI 4-32-03 & joints & fittings to be in accordance with WI 4-32-04. Other approved pipe materials to be in accordance with their relevant BS. Manhole covers & frames shall be manufactured in cast iron or ductile iron & shall comply with requirements of BS EN 124 & shall be kite marked or equivalent. Where there is no intermediate manhole between the start of a surface water pipe run and the soakaway the gradient of the run shall be not less than 1 : 60. 10. All completed work shall be suitably protected from damage by construction work. Damaged drainage will not be accepted. It is recommended that no heavy loading or underground work is permitted above or near unprotected drainage, and that dumpers, trucks, fork lifts or other heavy vehicles are not driven along or near pipe runs. P1 07/09/2023 Issued for comments NN / DE Description By / Chk Rev Date **PRP**: consulting engineers & surveyors Catherine HouseTelephone: 01604 889 870LeicesterOld Harborough Roadnorthampton@prp.uk.comNorthamptonBrixworth, NN6 9BXwww.prp.uk.comLondon engineering excellence [ creating advantage Client: Cartwright Homes Ltd. Architect: Hayward Architects Ltd. Project: Proposed Housing Woodlands Lane, Bedworth CV12 0NN Title: Section Through Flood Compensation Swale, Concrete Slab and Attenuation Tank Status: PRELIMINARY NN Date: June 2022 Engineer: Scales @ A1: NN Drawn: As Shown DE Checked: Project No: 82162 Drg No: 106 Rev: P1